


OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

STATION:	SALEM		
SYSTEM:	ADMINISTRATIVE		
TASK:	TCAF Adverse Environmental Conditions		
TASK NUMBER:	N1140430401		
JPM NUMBER:	14-01 NRC RO Admin A1-1		
ALTERNATE PATH:	☐	K/A NUMBER:	2.1.25
APPLICABILITY:	IMPORTANCE FACTOR: 3.9		
EO ☐	RO ☒	STA ☐	SRO ☒
EVALUATION SETTING/METHOD:	Classroom		
REFERENCES:	SC.OP-AB.ZZ-0001(Q) Rev. 18, Adverse Environmental Conditions, (rev. checked 9-3-15)		
TOOLS AND EQUIPMENT:			
VALIDATED JPM COMPLETION TIME:	30 min		
TIME PERIOD IDENTIFIED FOR TIME CRITICAL STEPS:	N/A		
Developed By:	G Gauding Instructor	Date:	7-23-15
Validated By:	S Bickhart / J Militti SME or Instructor	Date:	9-24-15
Approved By:	 Training Department	Date:	10-7-15
Approved By:	 Operations Department	Date:	10-9-15
ACTUAL JPM COMPLETION TIME:			
ACTUAL TIME CRITICAL COMPLETION TIME:			
PERFORMED BY:			
GRADE:	☐ SAT	☐ UNSAT	
REASON, IF UNSATISFACTORY:			
EVALUATOR'S SIGNATURE:	DATE:		

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

NAME: _____

DATE: _____

SYSTEM: Administrative

TASK: TCAF Adverse Environmental Conditions

TASK NUMBER: N1140430401

INITIAL CONDITIONS:

- Both Salem Units are operating at 100% power.
- All Unit 2 Circulators are in service.
- 13B and 12A Circulators are O/S.
- A report is received which states that wind speeds of 48 mph from direction 200° are expected onsite 8 hours from now.
- The CRS enters SC.OP-AB.ZZ-0001, Adverse Environmental Conditions.
- Current wind speed is 16 mph, and is expected to rise linearly over the next 8 hours.
- River temperature is 58°F.
- Outside air temperature is 65°F.
- The latest rolling weekly detritus loading is 2200 kg/million m³.
- River level over the next 8 hours is predicted to be:
 - T-0 89
 - T+1 89'
 - T+2 90'
 - T+3 90'
 - T+4 91'
 - T+5 92'
 - T+6 93'
 - T+7 94'
 - T+8 94'

The current time is 1100.

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

Initiating Cue:

INITIATING CUE:

Determine the required status of the reactors for the remainder of the shift as shown below by determining the Circulating Water Degradation Index (CWDI), Attachment 3, for BOTH units as directed in Section 3.11.

Assume the units will be maintained in the **HIGHEST** Mode allowed.

<u>Time</u>	<u>Unit 1 Mode</u>	<u>Unit 2 Mode</u>
1100		
1200		
1300		
1400		
1500		
1600		
1700		
1800		
1900		

Successful Completion Criteria:

1. All critical steps completed
2. All sequential steps completed in order
3. All time-critical steps completed within allotted time
4. JPM completed within validated time. Completion time may exceed the validated time if satisfactory progress is being made (and NRC concurrence is obtained).

Task Standard for Successful Completion:

1. Determines Unit 1 must be in MODE 2 by 1500, and Unit 2 must be in MODE 2 by 1600.

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: TCAF Adverse Environmental Conditions

*	STEP NO.	STEP (* Denotes a Critical Step)	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
		Provide a blank copy of SC.OP-AB.ZZ-0001.			
	3.1	<u>IF AT ANY TIME</u> Chemistry-Environmental or Rad-Waste Supervisor reports that River Grass Assessment samples can <u>NOT</u> be obtained because of natural or plant events, THEN INITIATE SC.OP-AB.ZZ-0003(Q), Component Biofouling.	Marks step N/A.		
	3.2	IF any of the entry conditions are met, THEN PERFORM the appropriate step(s): <u>IF</u> Wind Speeds of >30 mph (sustained) from sector between 140 degrees (SE) to 240 degrees (WSW) are predicted to occur within the next 8 hours, THEN GO TO Step 3.11 (Pg. 15).	Determines from initial conditions that wind speeds of >30 mph from sector between 140 degrees (SE) to 240 degrees (WSW) are predicted to occur within the next 8 hours, and GOES TO Step 3.11 (Pg. 15).		
	3.11.1	<u>IF</u> Wind Speeds of >30 mph (sustained) from sector between 140 degrees (SE) to 240 degrees (WSW) are predicted to occur within the next 8 hours, THEN COMPLETE Attachment 3, Circulating Water Degradation Index (CWDI), every hour until this criteria is no longer met.	Determines Wind Speeds of >30 mph from sector between 140 degrees (SE) to 240 degrees (WSW) are predicted to occur within the next 8 hours, and completes Attachment 3, Circulating Water Degradation Index.		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: TCAF Adverse Environmental Conditions

*	STEP NO.	STEP (* Denotes a Critical Step)	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
*	Att. 3 Page 1		Completes Attachment 3 for Unit 1 with the following numbers: Detritus Points: 2 pts for every hour Circulator Points: 1 pt every hour; Wind Wind Speed Points: 1 pt for every hour T+0 –T+5; 2 pts for T+6 – T+8. River Level Points: 0 pts thru T+5, 1 pt for T+6, 2 pts for T+7 -T+8. Total Points: 4 pts thru T+5, 6 pts for T+6, 7 pts for T+7 –T+8.		
*	Att. 3 Page 2		Completes Attachment 3 for Unit 1 with the following numbers: Detritus Points: 2 pts for every hour Circulator Points: 0 points every hour. Wind Speed Points: 1 pt for every hour T+0 –T+5; 2 pts for T+6 – T+8. River Level Points: 0 pts thru T+5, 1 pt for T+6, 2 pts for T+7 -T+8. Total Points: 3 pts thru T+5, 5 pts for T+6, 6 pts for T+7 – T+8.		
*	Att. 3 Page 3		Determines CWDI RED rating at T+6 (1700) for Unit 1 and T+7 for Unit 2 (1800)		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: TCAF Adverse Environmental Conditions

*	STEP NO.	STEP (* Denotes a Critical Step)	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
*	3.11.2	IF the predicted CWDI Rating is RED at any time within the next 8 hours, THEN PERFORM the following: A. PLACE the applicable Unit(s) in Mode 2 or Mode 3 at least 2 hours prior to the time the CWDI Rating is predicted RED.	CWDI RED rating requires placing unit in at least MODE 2 two hours prior to the RED rating. Determines Unit 1 must be in MODE 2 at 1500, and Unit 2 in MODE 2 by 1600.		
		Terminate the JPM when the completed tear off sheet and procedure are returned.			

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE


JOB PERFORMANCE MEASURE VALIDATION CHECKLIST

NOTE: All steps of this checklist should be performed upon initial validation. Prior to JPM usage, revalidate JPM using steps 8 and 11 below.

- AS 1. Task description and number, JPM description and number are identified.
- AS 2. Knowledge and Abilities (K/A) references are included.
- AS 3. Performance location specified. (in-plant, control room, or simulator)
- AS 4. Initial setup conditions are identified.
- AS 5. Initiating and terminating Cues are properly identified.
- AS 6. Task standards identified and verified by SME review.
- AS 7. Critical steps meet the criteria for critical steps and are identified with an asterisk (*).
- AS 8. Verify the procedure referenced by this JPM matches the most current revision of that procedure: Procedure Rev. 18 Date 8/17/2015
- AS 9. Pilot test the JPM:
a. verify Cues both verbal and visual are free of conflict, and
b. ensure performance time is accurate.
- _____ 10. If the JPM cannot be performed as written with proper responses, then revise the JPM.
- _____ 11. When JPM is revalidated, SME or Instructor sign and date JPM cover page.

SME/Instructor:  E. Bickel

Date: 9/24/15

SME/Instructor:  M. L. H.

Date: 9-24-15

SME/Instructor: _____

Date: _____

INITIAL CONDITIONS:

- Both Salem Units are operating at 100% power.
- All Unit 2 Circulators are in service.
- 13B and 12A Circulators are O/S.
- A report is received which states that wind speeds of 48 mph from direction 200° are expected onsite 8 hours from now.
- The CRS enters SC.OP-AB.ZZ-0001, Adverse Environmental Conditions.
- Current wind speed is 16 mph, and is expected to rise linearly over the next 8 hours.
- River temperature is 58°F.
- Outside air temperature is 65°F.
- The latest rolling weekly detritus loading is 2200 kg/million m³.
- River level over the next 8 hours is predicted to be:
 - T-0 89
 - T+1 89'
 - T+2 90'
 - T+3 90'
 - T+4 91'
 - T+5 92'
 - T+6 93'
 - T+7 94'
 - T+8 94'

The current time is 1100.

INITIATING CUE:

Determine the required status of the reactors for the remainder of the shift as shown below by determining the Circulating Water Degradation Index (CWDI), Attachment 3, for BOTH units as directed in Section 3.11.

Assume the units will be maintained in the **HIGHEST** Mode allowed.

<u>Time</u>	<u>Unit 1 Mode</u>	<u>Unit 2 Mode</u>
1100		
1200		
1300		
1400		
1500		
1600		
1700		
1800		
1900		