

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

STATION:	SALEM		
SYSTEM:	ADMINISTRATIVE		
TASK:	Review a completed surveillance to demonstrate Operability of 21 CFCU		
TASK NUMBER:	N1230300302		
JPM NUMBER:	11-01 NRC SRO Admin A1-1		
ALTERNATE PATH:	☒	K/A NUMBER:	2.1.25
APPLICABILITY:		IMPORTANCE FACTOR:	
EO ☐	RO ☐	STA ☐	SRO ☒
EVALUATION SETTING/METHOD:	Classroom		
REFERENCES:	S2.OP-ST.CBV-0003, Rev. 17 (checked 8-14-12)		
TOOLS AND EQUIPMENT:			
VALIDATED JPM COMPLETION TIME:	12 min		
TIME PERIOD IDENTIFIED FOR TIME CRITICAL STEPS:	N/A		
Developed By:	G Gauding Instructor	Date:	8-14-12
Validated By:	A Crampton SME or Instructor	Date:	9-10-12
Approved By:	Training Department	Date:	
Approved By:	Operations Department	Date:	

ACTUAL JPM COMPLETION TIME:	
ACTUAL TIME CRITICAL COMPLETION TIME:	
PERFORMED BY:	
GRADE:	☐ SAT ☐ UNSAT
REASON, IF UNSATISFACTORY:	
EVALUATOR'S SIGNATURE:	DATE:

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

NAME: _____

DATE: _____

{PRIVATE }SYSTEM: Administrative

TASK: Review a completed surveillance to demonstrate Operability of 21 CFCU

TASK NUMBER: N1230300302

INITIAL CONDITIONS: 21 CFCU was returned from corrective maintenance. S2.OP-ST.CBV-0003, Containment Systems - Containment Cooling was performed for the Operability Retest.

INITIATING CUE: You have been directed to review the surveillance for completeness and accuracy IAW Step 5.3.4.

Document any discrepancies that you identify and/or actions that you would take on Attachment 8, Section 1.0, Comments.

{PRIVATE }Successful Completion Criteria:

1. All critical steps completed
2. All sequential steps completed in order
3. All time-critical steps completed within allotted time
4. JPM completed within validated time. Completion time may exceed the validated time if satisfactory progress is being made (and NRC concurrence is obtained).

Task Standard for Successful Completion:

1. Identify that the Minimum Flow Rate recorded on Attachment 1, page 1 of 1, Section 3.0, for 91 psid is incorrectly recorded as 1638. Identify the correct Minimum Flow Rate should be 1683.
2. Identify that the actual Cooling Water Flow Rate (1675) is below the Minimum Flow Rate required as shown on Attachment 1 and Exhibit 1, and the surveillance is UNSAT vs SAT.

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: Review a completed surveillance to demonstrate Operability of 21 CFCU

*	STEP NO.	STEP (* Denotes a Critical Step)	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
			Provide completed S2.OP-ST.CBV-0003 surveillance.		
			Reviews procedure.		
*			Identifies that the Minimum Flow Rate recorded on Attachment 1, page 1 of 1, Section 3.0, for 91 psid is incorrectly recorded as 1638. (This was due to operator performing ST rounding down as opposed to rounding up IAW P&L 3.4.)		
*			Identifies correct value for Minimum Flow Required as 1683.		
*			Cue: <u>IF</u> candidate only determines flow is wrong, <u>THEN</u> ask candidate to determine correct flow.		
			Identifies that the actual Cooling Water Flow Rate of 1675 gpm is below the Minimum Flow Rate of 1683 as shown on Exhibit 1 and the ST is UNSAT.		
			When candidate turns in JPM, ensure they have provided correct flow as per Cue above, then state JPM is complete.		

OPERATOR TRAINING PROGRAM{PRIVATE }
JOB PERFORMANCE MEASURE

TQ-AA-106-0303
Revision 4

JOB PERFORMANCE MEASURE VALIDATION CHECKLIST

NOTE: All steps of this checklist should be performed upon initial validation. Prior to JPM usage, revalidate JPM using steps 8 and 11 below.

- _____ 1. Task description and number, JPM description and number are identified.
- _____ 2. Knowledge and Abilities (K/A) references are included.
- _____ 3. Performance location specified. (in-plant, control room, or simulator)
- _____ 4. Initial setup conditions are identified.
- _____ 5. Initiating and terminating Cues are properly identified.
- _____ 6. Task standards identified and verified by SME review.
- _____ 7. Critical steps meet the criteria for critical steps and are identified with an asterisk (*).
- _____ 8. Verify the procedure referenced by this JPM matches the most current revision of that procedure: Procedure Rev. _____ Date _____
- _____ 9. Pilot test the JPM:
 - a. verify Cues both verbal and visual are free of conflict, and
 - b. ensure performance time is accurate.
- _____ 10. If the JPM cannot be performed as written with proper responses, then revise the JPM.
- _____ 11. When JPM is revalidated, SME or Instructor sign and date JPM cover page.

SME/Instructor: _____

Date: _____

SME/Instructor: _____

Date: _____

SME/Instructor: _____

Date: _____

INITIAL CONDITIONS:

21 CFCU was returned from corrective maintenance. S2.OP-ST.CBV-0003, Containment Systems - Containment Cooling was performed for the Operability Retest.

INITIATING CUE:

You have been directed to review the surveillance for completeness and accuracy IAW Step 5.3.4.

Document any discrepancies that you identify and/or actions that you would take on Attachment 8, Section 1.0, Comments.