

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

STATION:	SALEM		
SYSTEM:	ADMINISTRATIVE		
TASK:	Direct Actions for Spent Fuel Movement (Determine work which would require suspension of Fuel Movement)		
TASK NUMBER:	N1120760102		
JPM NUMBER:	11-01 NRC SRO Admin A1-2		
ALTERNATE PATH:	☐	K/A NUMBER:	2.1.42
		IMPORTANCE FACTOR:	3.4
APPLICABILITY:		RO	SRO
EO ☐	RO ☐	STA ☐	SRO ☒
EVALUATION SETTING/METHOD:	Classroom		
REFERENCES:	S2.OP-IO.ZZ-0010, Rev. 31 , S2.OP-SO.CH-0001 Rev 30, S2.OP-SO.SW-0005 Rev 41, S2.OP-SO.DG-0005, Rev.6 (all checked 8-14-12) Salem Tech Specs		
TOOLS AND EQUIPMENT:			
VALIDATED JPM COMPLETION TIME:	30 min		
TIME PERIOD IDENTIFIED FOR TIME CRITICAL STEPS:	N/A		
Developed By:	G Gauding Instructor	Date:	8-14-12
Validated By:	A Crampton SME or Instructor	Date:	9-10-12
Approved By:	Training Department	Date:	
Approved By:	Operations Department	Date:	
ACTUAL JPM COMPLETION TIME:			
ACTUAL TIME CRITICAL COMPLETION TIME:			
PERFORMED BY:			
GRADE: ☐ SAT ☐ UNSAT			
REASON, IF UNSATISFACTORY:			
EVALUATOR'S SIGNATURE:			DATE:

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

NAME: _____

DATE: _____

{PRIVATE
}SYSTEM:

Administrative

TASK:

Direct Actions for Spent Fuel Movement (Determine work which would require suspension of Fuel Movement)

TASK NUMBER:

N1120760102

INITIAL
CONDITIONS:

Salem Unit 2 is operating at 99% power, coasting down into a refueling outage which will start in 2 weeks.
Irradiated fuel movement is **in progress** in the Spent Fuel Pool IAW S2.OP-IO.ZZ-0010, Spent Fuel Pool Manipulations, and will continue without interruption for the next 8 hours, at which time it will terminate.
The unit has no active Tech Spec LCOs.
The current time is 0800.

INITIATING CUE:

You have been directed to review the upcoming Unit 2 work for the shift and determine which activities would require suspension of fuel movement before that activity could be performed.

Work scheduled for today and expected duration

0900- 22 SW pump packing replacement (48 hours)

1000- 2A EDG Monthly surveillance run (2 hours)

1300- 21 Chiller compressor oil change (8 hours)

1400- Delivery of New Fuel into the Fuel Handling Building for upcoming refueling outage (6 hours)

{PRIVATE }Successful Completion Criteria:

1. All critical steps completed
2. All sequential steps completed in order
3. All time-critical steps completed within allotted time
4. JPM completed within validated time. Completion time may exceed the validated time if satisfactory progress is being made (and NRC concurrence is obtained).

Task Standard for Successful Completion:

1. Determination that 22 SW pump work, 2A EDG surveillance, and 21 Chiller work do NOT require suspension of fuel movement.
2. Determination that New Fuel delivery DOES required suspension of fuel movement.

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____
DATE: _____

System: ADMINISTRATIVE

Task: Direct Actions for Spent Fuel Movement (Determine work which would require suspension of Fuel Movement)

*	STEP NO.	STEP * Denotes a Critical Step	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
			Provide marked up copy of S2.OP-IO.ZZ-0010, Spent Fuel Pool Manipulations. All other procedures are located in the Salem LORT classroom, where this JPM should be administered one at a time.		
			Notes: TSAS 3.8.1.2 applies during Modes 5 and 6 and during movement of irradiated fuel, and only requires one EDG. Only one FHB exhaust fan is required to be backed by an operable EDG (IOP-10 page 15) Operable SFP pumps only need one of them backed by operable EDG. (IOP-10 page 15)		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: Direct Actions for Spent Fuel Movement (Determine work which would require suspension of Fuel Movement)

*	STEP NO.	STEP * Denotes a Critical Step	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
			Notes: TSAS 3.7.10 allows a chiller to be taken out if movement of irradiated fuel is already on-going, and gives 14 days to restore it. 3.0.4 does NOT apply. Two SW pumps are required to be operable, one of which is EDG backed. (IOP-10 page 16.) Of the 5 remaining SW pumps, 4 are powered from B and C vital and their EDGs remain operable. Service Water Tech Specs will not be entered for a single SW pump being inoperable.		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: Direct Actions for Spent Fuel Movement (Determine work which would require suspension of Fuel Movement)

*	STEP NO.	STEP * Denotes a Critical Step	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
* * * *			Determines that: 22 SW pump does <u>NOT</u> require suspension of fuel movement. 2A EDG surveillance does <u>NOT</u> require suspension of fuel movement. 21 Chiller oil replacement does <u>NOT</u> require suspension of fuel movement. New Fuel delivery <u>DOES</u> require suspension of fuel movement (based on requirement that the Truck Bay door to the Fuel Handling building must remain closed, page 17 of 33) Evaluator ensure tear off sheet has candidates name and status for each of the four work activities.		

Additional information: TSAS 3.7.10 requires 3 Operable Chillers. The ACTIONS associated with having one chiller inoperable are found on page 3/4 7-29 under Modes 5 and 6 or during movement of irradiated fuel assemblies. The ACTION requires you to do: a.1 and a.2 or take action 3, which is suspend core alts and movement of irradiated fuel. Action a.1 would be performed, and a.2 states the chiller has 14 days to be returned to operable before the action of a.3 is required. Step 3.10 of S2.OP-IO.ZZ-0010 Spent Fuel Pool Manipulations, says to refer to TSAS 3.7.10 for required actions if a chiller is inoperable.

Name: _____

OPERATOR TRAINING PROGRAM{PRIVATE }
JOB PERFORMANCE MEASURE

JOB PERFORMANCE MEASURE VALIDATION CHECKLIST

NOTE: All steps of this checklist should be performed upon initial validation. Prior to JPM usage, revalidate JPM using steps 8 and 11 below.

- _____ 1. Task description and number, JPM description and number are identified.
- _____ 2. Knowledge and Abilities (K/A) references are included.
- _____ 3. Performance location specified. (in-plant, control room, or simulator)
- _____ 4. Initial setup conditions are identified.
- _____ 5. Initiating and terminating Cues are properly identified.
- _____ 6. Task standards identified and verified by SME review.
- _____ 7. Critical steps meet the criteria for critical steps and are identified with an asterisk (*).
- _____ 8. Verify the procedure referenced by this JPM matches the most current revision of that procedure: Procedure Rev. _____ Date _____
- _____ 9. Pilot test the JPM:
 - a. verify Cues both verbal and visual are free of conflict, and
 - b. ensure performance time is accurate.
- _____ 10. If the JPM cannot be performed as written with proper responses, then revise the JPM.
- _____ 11. When JPM is revalidated, SME or Instructor sign and date JPM cover page.

SME/Instructor: _____

Date: _____

SME/Instructor: _____

Date: _____

SME/Instructor: _____

Date: _____

Name: _____

INITIAL CONDITIONS:

Salem Unit 2 is operating at 99% power, coasting down into a refueling outage which will start in 2 weeks.

Irradiated fuel movement is **in progress** in the Spent Fuel Pool IAW S2.OP-IO.ZZ-0010, Spent Fuel Pool Manipulations, and will continue without interruption for the next 8 hours, at which time it will terminate.

The unit has no active Tech Spec LCOs.

The current time is 0800.

INITIATING CUE:

You have been directed to review the upcoming Unit 2 work for the shift and determine which activities would require suspension of fuel movement before that activity could be performed.

Work scheduled for today and expected duration

0900- 22 SW pump packing replacement (48 hours)

1000- 2A EDG Monthly surveillance run (2 hours)

1300- 21 Chiller compressor oil change (8 hours)

1400- Delivery of New Fuel into the Fuel Handling Building for upcoming refueling outage (6 hours)