


OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

STATION:	SALEM		
SYSTEM:	ADMINISTRATIVE		
TASK:	Determine required actions upon Radioactive Effluent Monitor failure		
TASK NUMBER:	N1200010301		
JPM NUMBER:	11-01 NRC SRO Admin A3		
ALTERNATE PATH:	☐	K/A NUMBER:	2.3.11
APPLICABILITY:		IMPORTANCE FACTOR:	4.3
EO ☐	RO ☐	STA ☐	SRO ☒
EVALUATION SETTING/METHOD:	Classroom		
REFERENCES:	Salem ODCM, Salem Tech Specs, S1.OP-SO.WL-0001, Release of 11 CVCS Monitor Tank, S1.OP-SO.WG-0011, Release of 14 GDT, S1.OP-SO.CBV-0002 Containment Pressure-Vacuum Relief System		
TOOLS AND EQUIPMENT:			
VALIDATED JPM COMPLETION TIME:	25 min		
TIME PERIOD IDENTIFIED FOR TIME CRITICAL STEPS:	N/A		
Developed By:	G Gauding Instructor	Date:	8-15-12
Validated By:	A Crampton SME or Instructor	Date:	9-10-12
Approved By:	 Training Department	Date:	9/12/12
Approved By:	 Operations Department	Date:	9/11/12
ACTUAL JPM COMPLETION TIME:			
ACTUAL TIME CRITICAL COMPLETION TIME:			
PERFORMED BY:			
GRADE:	☐ SAT	☐ UNSAT	
REASON, IF UNSATISFACTORY:			
EVALUATOR'S SIGNATURE:			DATE:

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

SYSTEM: Administrative

TASK: Determine required actions upon Radioactive Effluent Monitor failure

TASK NUMBER: N1200010301

INITIAL CONDITIONS: Unit 1 is operating at 100% power.

Radiation Monitor 1R12A- Containment Noble Gas, failed its Source Check when preparing to perform a normal Containment Pressure Relief IAW S1.OP-SO.CBV-0002, Containment Pressure-Vacuum Relief System Operation.

11 CVCS Monitor Tank is ready for release.

14 Gas Decay Tank (GDT) is ready for release.

INITIATING CUE: Prior to initiating the Containment Pressure Relief, Rad Monitor 1R41D, Plant Vent Release Rate, indication fails high, and is confirmed as an instrument failure.

Determine the requirements, if any, which must be met to initiate:

- Containment Pressure Relief
- 11 CVCS Monitor Tank release
- 14 GDT release

List all compensatory actions, including times they must occur for each release to be initiated. If a release is prohibited from being initiated in this conditions then state that. If no additional restrictions apply to any of the releases then state that.

Successful Completion Criteria:

1. All critical steps completed
2. All sequential steps completed in order
3. All time-critical steps completed within allotted time
4. JPM completed within validated time. Completion time may exceed the validated time if satisfactory progress is being made (and NRC concurrence is obtained).

Task Standard for Successful Completion:

1. Determines additional compensatory measures apply for the Waste Gas Release and the Containment Pressure Relief per key.
2. Determines no additional compensatory actions required for Liquid Release.

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: Determine required actions upon Radioactive Effluent Monitor failure

*	STEP NO.	STEP * Denotes a Critical Step	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
		Note: There is no controlled copy of the Salem ODCM in the classroom. Ensure the Simulator copy is placed in classroom prior to starting JPM, or provide a copy to each candidate.			
		Evaluate the effect the combined failure of the 1R12A and the 1R41D have upon the initiation of Containment Pressure Relief, Waste Liquid Release, and Gaseous Releases.			
		Waste Gas Release	Determines ODCM 3.3.3.9 applies to Gaseous Effluent which directs actions per Table 3.3-13.		
			Determines Table 3.3-13, Instrument #1, Waste Gas Holdup System is applicable, which requires (1) 1R41A & D. Action 31 applies.		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: Determine required actions upon Radioactive Effluent Monitor failure

*	STEP NO.	STEP * Denotes a Critical Step	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
*			Action 31 states that with less than the minimum required Operable channels, the contents of the tank may be released provided that prior to the initiating the release: a. At least two independent samples of the tanks contents are analyzed, and b. At least two technically qualified memebers of the facility Staff independently verify the release rate calculations and discharge valving lineup; otherwise suspend release of radioactive effluents via this pathway. Additionally, S1.OP-SO.WG-0011, Discharge of 14 Gas Decay tank to Plant Vent, Section 3.0, Dose Estimates and Approval, Step 3.4.C (on page 18) states..." Grab samples are being obtained at least once per 8 hours AND analyzed for gaseous principal gamma emitters within 24 hours		
*			Determines that there is no restriction on performing Liquid Releases.		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: Determine required actions upon Radioactive Effluent Monitor failure

*	STEP NO.	STEP * Denotes a Critical Step	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
		Containment Pressure Relief	Determines that Precaution and Limitation 2.3 of S1.OP-SO.CBV-0001 directs operator to notify Chemistry to comply with the contingency actions associated with the ODCM prior to performing a Containment Pressure Relief.		
			Determines Table 3.3-13, Instrument #3, applies to the Containment Pressure Relief. With both channels (1R41A & D OR 1R12A) inoperable, Action 37 applies.		
* *			Action 37 states that with less than the minimum required Operable channels, Containment Pressure Reliefs may be performed provided that prior to initiating the release: a. At least two independent samples of the tanks contents are analyzed, and b. At least two technically qualified members of the facility Staff independently verify the release rate calculations, otherwise suspend release of radioactive effluents via this pathway.		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

System: ADMINISTRATIVE

Task: Determine required actions upon Radioactive Effluent Monitor failure

*	STEP NO.	STEP * Denotes a Critical Step	STANDARD	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
		Terminate JPM when all paperwork is handed in.			

Note to Evaluator: JPM modeled after Pilgrim Jan 2011 NRC Exam SRO Admin JPM RC.

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

JOB PERFORMANCE MEASURE VALIDATION CHECKLIST

NOTE: All steps of this checklist should be performed upon initial validation. Prior to JPM usage, revalidate JPM using steps 8 and 11 below.

- h* 1. Task description and number, JPM description and number are identified.
- h* 2. Knowledge and Abilities (K/A) references are included.
- h* 3. Performance location specified. (in-plant, control room, or simulator)
- h* 4. Initial setup conditions are identified.
- h* 5. Initiating and terminating Cues are properly identified.
- h* 6. Task standards identified and verified by SME review.
- h* 7. Critical steps meet the criteria for critical steps and are identified with an asterisk (*).
- h* 8. Verify the procedure referenced by this JPM matches the most current revision of that procedure: Procedure Rev. 31 Date 5/17/02
- h* 9. Pilot test the JPM:
a. verify Cues both verbal and visual are free of conflict, and
b. ensure performance time is accurate.
- n/a* 10. If the JPM cannot be performed as written with proper responses, then revise the JPM.
11. When JPM is revalidated, SME or Instructor sign and date JPM cover page.

SME/Instructor: _____

Date: _____

SME/Instructor: _____

Date: _____

SME/Instructor: _____

Date: _____

INITIAL CONDITIONS:

Unit 1 is operating at 100% power.

Radiation Monitor 1R12A- Containment Noble Gas, failed its Source Check when preparing to perform a normal Containment Pressure Relief IAW S1.OP-SO.CBV-0002, Containment Pressure-Vacuum Relief System Operation.

11 CVCS Monitor Tank is ready for release.

14 Gas Decay Tank (GDT) is ready for release.

INITIATING CUE:

Prior to initiating the Containment Pressure Relief, Rad Monitor 1R41D, Plant Vent Release Rate, indication fails high, and is confirmed as an instrument failure.

Determine the requirements, if any, which must be met to initiate:

- Containment Pressure Relief
- 11 CVCS Monitor Tank release
- 14 GDT release

List all compensatory actions, including times they must occur for each release to be initiated. If a release is prohibited from being initiated in this conditions then state that. If no additional restrictions apply to any of the releases then state that.