

PLANT SYSTEMS

3/4.7.7 AUXILIARY BUILDING VENTILATION SYSTEM

LIMITING CONDITION FOR OPERATION

3.7.7 At least two supply fans, and three exhaust fans shall be OPERABLE(*) to maintain the Auxiliary Building at slightly negative pressure.

-----NOTE-----

The intermittent opening of the Auxiliary Building pressure boundary causing a loss of negative pressure may be performed under administrative controls.

APPLICABILITY: At all times.

ACTION:

Modes 1 thru 4

- a) With one supply fan and/or one exhaust fan inoperable, restore the fan(s) to OPERABLE status within 14 days or be in HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.
- b) With two supply and/or two exhaust fans inoperable restore at least one inoperable supply and two exhaust fans to operable status within 24 hours or be in HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.
- c) With the Auxiliary Building pressure not maintained slightly negative, restore the building to slightly negative pressure within the next 4 hours or be in HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours.

During CORE ALTERATIONS

- d) With the Auxiliary Building pressure not maintained slightly negative, restore the Auxiliary Building to slightly negative pressure within the next 4 hours or suspend all operations involving CORE ALTERATIONS.

At all times

- e) With the Auxiliary Building pressure not maintained slightly negative, suspend all operations involving radioactive gaseous releases via the Auxiliary Building immediately.

(*) One of the supply fans may be considered OPERABLE with its auto start circuit administratively controlled (removed from service) to prevent more than one supply fan from operating at any time.

PLANT SYSTEMS

SURVEILLANCE REQUIREMENTS

4.7.7 The above required Auxiliary Building Ventilation System shall be demonstrated OPERABLE:

- a) In accordance with the Surveillance Frequency Control Program by verifying negative pressure in the Auxiliary Building.
- b) In accordance with the Surveillance Frequency Control Program by starting each fan, from the control room, each fan operates for at least 15 minutes.
- c) In accordance with the Surveillance Frequency Control Program by verifying that the system starts following a Safety Injection Test Signal.

PLANT SYSTEMS
SURVEILLANCE REQUIREMENTS

THIS PAGE LEFT BLANK INTENTIONALLY